

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
A	Earth work				
1	Earth excavation in ordinary soil				
	Earth work in excavation up to 1.5m depth in ordinary soil including dressing & levelling the bed & depositing the excavated materials within 50m. initial lead & 1.5m. initial lift with all cost, conveyance, tools & plants, labour, complete as per the direction of Engg.-in-charge.	Cum	1,000		
2	Earth excavation in gravelly soil				
	Earth work in excavation up to 1.5m depth in gravelly soil including dressing & levelling the bed & depositing the excavated materials within 50m. initial lead & 1.5m. initial lift with all cost, conveyance, tools & plants, labour, complete as per the direction of Engg.-in-charge.	Cum	100		
3	Earth excavation/ levelling & dressing etc by JCB				
	Earth excavation/ levelling & dressing etc by using JCB in mechanized manner including all costs, conveyance, fuels, mobilisation & demobilisation at site, T&P & labour charges etc, complete in all respect as per the direction of Engineer-in-charge as and when required.	Hour	50		
4	Back filling / plinth filling with excavated earth within 50m lead				
	Earth work in back filling of foundation/ pits / trenches etc including dressing & levelling with excavated earth within initial lead of 50 meters with all costs, conveyance, T&P, labour complete as per the direction of Engg.-in-charge.	Cum	500		
5	Back filling/ plinth filling with transported soil				
	Earth work in back filling of foundation/ pits / trenches etc including dressing & levelling with transported soil within lead of 5 kilometres meters including all costs, conveyance, T&P, labour, excavation at borrow pit, royalty if any, loading and unloading, complete as per the direction of Engg.-in-charge.	Cum	100		
6	Supplying & Spreading Moorum				
	Collecting, stacking and conveying from stack and spreading moorum consolidation with hand ramming including all cost and conveyance of moorum, watering, T& P, labour, royalty etc. complete as per direction of Engineer-in-charge.	Cum	200		
7	Transportation of debris				
	Transportation of debris / surplus spoil away from work site upto a lead of 5 kilometres by tractor including all cost, conveyance, fuels, loading & unloading, labour charges etc complete as per the direction of Engg.-in-charge.	Cum	1,000		
8	Supplying & Filling Sand				
	Supplying and Filling of sand in foundation and plinth, watering and ramming including all cost, conveyance, T& P, royalty and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	250		
B	Masonry work				
9	Ash brick masonry (1:6) foundation				
	Ash brick masonry in cement mortar(1:6) in foundation and plinth for all type of works of all thickness including all cost, splays cutting, watering, curing, conveyance, T & P, Scaffoldings, royalty of all materials and labour charges etc. complete as per direction of Engg.-in-charge. (Ash brick will be supplied from Ash Brick Plant of OPGC free of cost. Contractor has to arrange his own conveyance for transportation to Site)	Cum	700		
10	Ash brick masonry (1:6) in Superstructure				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Ash brick masonry in cement mortar(1:6) in Superstructure for all type of works of all thickness including all cost, splays cutting, watering, curing, conveyance, T & P, Scaffoldings, royalties of all materials and labour charges etc. complete as per direction of Engg.-in-charge. (Ash brick will be supplied from Ash Brick Plant of OPGC free of cost. Contractor has to arrange his own conveyance for transportation to Site)	Cum	300		
C	Cement concrete work				
11	PCC (1:4:8) 40mm graded HG metal				
	Cement Concrete(1:4:8) by using 40mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials, scaffolding & labour charges etc. complete as per direction of Engg.	Cum	200		
12	PCC (1:3:6) 12 to 20mm graded HG chips				
	Cement Concrete (1:3:6) by using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T&P, royalties of all materials, scaffolding & labour charges etc. complete as per direction of Engg.-in-Charge.	Cum	10		
13	PCC (1:2:4) 12 to 20mm graded HG chips				
	Cement Concrete (1:2:4) using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials required for the work, Scaffolding & labour charges etc complete as per direction of Engineer-in-charge	Cum	200		
14	RCC (1:2:4) 12 to 20mm graded HG Chips				
	Reinforced cement concrete (1:2:4) for all type of work using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T&P, royalties of all materials required for the work, Scaffolding & labour charges etc. Complete as per direction of Engineer-in-charge. Reinforcement rod, form work (centering and shuttering) will be paid separately.	Cum	20		
15	RCC (1:1.5:3) 12 to 20mm graded HG Chips				
	Reinforced cement concrete(1:1.5:3) for all type of work using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials required for the work, Scaffolding & labour charges etc complete as per the direction of Engineer-in-charge. Reinforcement rod and centering and shuttering will be paid separately.	Cum	50		
16	Lift charges for Cement Concrete Work above Ground Floor upto First Floor				
	Extra for Lift charges for all type of cement concrete work above ground floor upto First Floor or a part there of.	Cum	15		
D	Form work				
17	Centering and shuttering work (Form work) - Roof Slab				
	Providing and fixing strong, rigid, smooth, levelled, and plumbed CENTERING AND SHUTTERING (Form work) including dismantling the same after the required intervals from the date of casting including cost of all materials, labour, conveyance, loading and unloading, royalties, scaffolding, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge - for RCC Floor and roof slabs, landings, balconies, projecting sun shades and chajjas upto 4.3 meter height	Sqm	30		
18	Centering and shuttering work (Form work) - Mass Concrete / precast slab				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing and fixing strong, rigid, smooth, levelled, and plumbed CENTERING AND SHUTTERING (Form work) including dismantling the same after the required intervals from the date of casting including cost of all materials, labour, conveyance, loading and unloading, royalties, scaffolding, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge - for RCC Foundation and Footing bases of column, mass concrete, precast slabs etc	Sqm	500		
19	Centering and shuttering work (Form work) - RCC Beam / Column				
	Providing and fixing strong, rigid, smooth, levelled, and plumbed CENTERING AND SHUTTERING (Form work) including dismantling the same after the required intervals from the date of casting including cost of all materials, labour, conveyance, loading and unloading, royalties, scaffolding, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge - for RCC Beams, column, girder, and bressmer etc	Sqm	20		
20	Centering and shuttering work (Form work) - Lintels				
	Providing and fixing strong, rigid, smooth, levelled, and plumbed CENTERING AND SHUTTERING (Form work) including dismantling the same after the required intervals from the date of casting including cost of all materials, labour, conveyance, loading and unloading, royalties, scaffolding, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge - for RCC Lintels	Sqm	20		
E	Steel work				
21	M.S. Reinforcement bar cutting, binding and placing				
	Straightening, cutting, bending, binding, tying and placing of M.S. Reinforcement bars (Plain or Tor) in position including all cost of M.S. Reinforcement bars & binding wire (20 to 22 gauge), conveyance, T & P, Scaffoldings, labour charges etc. complete as per direction of EIC.	Qntl	50		
22	Supplying & fixing of chicken mesh/ welded mesh jali				
	Supplying, cutting to size, fitting & fixing of chicken mesh/ welded mesh jali 25x25x11 gauge for all type of work including all cost of material, conveyance, labour charges and T & P, scaffoldings, sundries etc. complete as per direction of Engineer-in-charge.	Sqm	50		
23	Supplying & Fixing 22 gauge GCI sheet				
	Supplying & Fixing of 22 gauge GCI sheet in roofing, walling, ridging etc of SAIL / Equivalent make with all required GI J/L hooks, bitumen washers, GI cup washer, nuts and bolts etc, drilling holes for fixing, including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	Sqm	100		
24	Supplying & Fixing Colour Coated Trapezoidal sheet				
	Supply and fixing of colour coated trapezoidal sheets of 0.5mm thick of Everest / Bhusan/ equivalent make including cost of 55x8mm self driven screws as required for fixing the sheets complete including conveyance, lead and lift at site & labour charge required for the work all complete as per the direction of the Engineer-In-Charge.	Sqm	400		
25	Fabrication/ erection of iron work				
	Supplying, Fabrication and erection of all type of Mild steel Iron work (sectional weight upto 19.8 kg/m) for all type of structures, sheds, grills, doors, fencing posts etc with approved quality (SAIL/ Equivalent make) steel structural, angles, channels, plates of all sections at all levels and elevations, painting with 2 (two) coats of high gross enamel paint over a coat of red oxide primer including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In-Charge	Kg	5,000		
26	Repair of M.S doors / grills/ shutters				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Labour Charges for Repairing of all type of steel doors, grills, shutters etc on position or at workshop by cutting out the damaged and corroded steel structural, fixing of new steel structural as required by welding (to be paid separately) at all levels and elevations, painting with 2 (two) coats of high gross enamel paint over a coat of red oxide primer including all cost of materials except steel, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	Kg	7,000		
F	Cement Finish Work				
27	12mm Cement plaster (1:6)				
	Providing 12mm. thick cement plaster in cement mortar (1:6) over masonry/ CC work, finished smooth after racking out joints including all cost, watering, curing, conveyance, T& P, royalties of all materials, scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	7,000		
28	16mm Cement plaster (1:6)				
	16mm. thick cement plaster in cement mortar (1:6) over masonry/ CC work, finished smooth after racking out joints including all cost, watering, curing, conveyance, T & P, royalties of all materials, scaffolding and labour charges etc. complete as per direction of engineer-in-charge	Sqm	3,000		
29	6mm thick Cement plaster (1:4)				
	6mm. thick cement plaster in cement mortar (1:4) for all type of ceiling plaster work, RCC Surface with deep chipping and slurry treatment, including all cost, watering, curing, conveyance, T & P, royalties of all materials, scaffolding and labour charges etc. complete as per direction of Engg.-in-charge.	Sqm	1,000		
30	Neat cement Punning				
	Extra for Neat cement punning over cement plaster work including all cost, watering, curing, conveyance, T & P, scaffolding and labour charges etc. complete as per direction of EIC.	Sqm	2,000		
G	Flooring Work				
31	25mm AS flooring (1:2:4) 6 to12mm graded aggregates				
	25mm. thick A.S. flooring in Cement Concrete (1:2:4) laid to required slope with 12mm down aggregates(6 to 12mm) hard granite crusher broken chips, finishing the top with cement slurry, including all cost, watering, curing, conveyance, T & P, royalties of all materials, scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	1,000		
32	40mm AS flooring (1:2:4) 6 to 12mm graded aggregates				
	40mm. thick A.S. flooring in Cement Concrete(1:2:4) laid in two layers to the required slope with 6 to12mm graded aggregates hard granite crusher broken chips, finishing the top with cement slurry, including all cost, watering, curing, conveyance, T & P, royalties of all materials, scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	800		
33	25mm Grading Concrete (1:2:2) on roof slab				
	Providing and laying 25mm thick grading concrete (1:2:2) on roof slab using 6mm and down graded size hard granite chips for old work including all cost, conveyance, royalties and labour charges etc complete as per the direction of the Engineer-In-Charge.	Sqm	500		
34	40mm Grading Concrete (1:2:4) on roof slab				
	Providing and laying 40mm thick grading concrete (1:2:4) on roof slab using 12mm and down graded size hard granite chips for old work including all cost, conveyance, royalties and labour charges etc complete as per the direction of the Engineer-In-Charge.	Sqm	40		
35	Ceramic Floor tiles 300mm to 500mm size				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing & fixing 8mm thick 300mm to 500mm Size Ceramic floor tiles of approved make (Somani / Nitco / Kajaria / Johnson / Regency/ equivalent) and approved shade and texture over a bed of average 20mm thick Cement Mortar (1:4) and joints with white cement / tile joint adhesives with required colour pigment including all cost, watering, curing, conveyance, T & P, royalties of all materials, and labour charges etc. complete as per the direction of engineer-in-charge	Sqm	200		
36	Ceramic Glazed tile in Skirting / Dado 200mm to 450mm size				
	Providing & fixing 6mm thick ceramic glazed tiles 200mm to 450 mm size of approved make (Somani / Nitco / Kajaria / Johnson / Regency/ equivalent) and approved shade and texture in skirting / dados fixed on average 12mm. thick cement plaster (1:3) and jointed with white cement / tile joint adhesives with required colour pigment including all cost, watering, curing, conveyance, T & P, royalties of all materials, and labour charges etc. complete as per the direction of engineer-in-charge.	Sqm	300		
37	Vitrified Floor tiles 600mm size				
	Providing & fixing Vitrified Floor tiles of 600mm x 600mm size of approved make (Somani / Nitco / Kajaria / Johnson / Regency/ equivalent) and approved shade and texture over a bed of average 20mm thick Cement Mortar (1:4) and joints with white cement / tile joint adhesives with required colour pigment including all cost, watering, curing, conveyance, T & P, royalties of all materials, and labour charges etc. complete as per the direction of engineer-in-charge	Sqm	100		
38	25mm chequered tiles flooring				
	Providing & fixing 25mm thick Chequered Tiles of approved make and shade in exterior floors / stairs etc over a bed of average 20mm thick cement mortar (1:4) and joints grouted with cement slurry with required Colour pigment including all cost, watering, curing, conveyance, T & P, royalties of all materials required for the work and labour charges etc complete as per direction of Engineer-in-charge.	Sqm	20		
39	Kodappa/ Kotta Stone tile Flooring				
	Providing & fixing 16 mm thick Kodappa / Kotta stone tile of approved quality and texture in platform/ stairs/ floors etc including surfacing, grinding and moulding the noses as required over a bed of average 20mm thick cement mortar (1:4) and joints grouted with cement slurry including all cost, watering, curing, conveyance, T & P, royalties of all materials required for the work and labour charges etc complete. as per direction of Engineer-in-charge.	Sqm	50		
40	Granite Stone tile Flooring				
	Providing & fixing 10 to 12 mm thick Granite stone tile of approved quality & Texture in platform/ stairs/ floors etc including surfacing, grinding and moulding the noses as required over a bed of average 20mm thick cement mortar (1:4) and joints grouted with cement slurry with required Colour pigment including all cost, watering, curing, conveyance, T & P, royalties of all materials required for the work and labour charges etc complete. as per direction of Engineer-in-charge.	Sqm	10		
41	Marble Stone Flooring				
	Providing & fixing 16 to 20mm thick Marble Stone of approved quality & texture in platform/ stairs/ floors etc including surfacing, grinding and moulding the noses as required over a bed of average 20mm thick cement mortar (1:4) and joints grouted with white cement slurry with required Colour pigment including all cost, watering, curing, conveyance, T & P, royalties of all materials required for the work and labour charges etc complete. as per direction of Engineer-in-charge.	Sqm	10		
42	Interlocking Paver Block of 60mm thick				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. including all cost of labour, material, conveyance, royalties, loading ,unloading, T&P etc. all complete as per the direction of Engineer-in-charge.	Sqm	500		
H	Decoration Work				
43	White washing 02 coats - Shell lime				
	White washing 02 coats on old / new surface using best quality shell lime including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,500		
44	Painting Snowcem (Cement base paint) two coats				
	Providing & Painting with Cement base paint (Super Snowcem) 02 (two) coats on old / new surface using approved Brand and shade Super Snowcem including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	5,000		
45	Painting Snowcem (Cement Base Paint) three coats				
	Providing & Painting with Cement base paint (Super Snowcem) 03 (three) coats on old / new surface using approved Brand and shade Super Snowcem including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,000		
46	Painting Weatherproof exterior emulsion paint 02 coats				
	Providing & Painting with Weatherproof Anti fungal Exterior emulsion Paint 02 (two) coats on old / new surface using approved Brand and shade Weatherproof paint (Asian / Dulux / Salimar / Berger) including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	4,000		
47	Painting Weatherproof exterior emulsion paint 02 coats over a coat of Primer				
	Providing and painting with weatherproof anti fungal exterior emulsion paint 02 (two) coats over a coat of primer on old / new surface using approved brand and shade weatherproof paint / primer (Asian / Dulux / Shalimar / Berger) including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including cost, conveyance, T&P, Scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	2,000		
48	Painting Distemper 01 coat				
	Providing & Painting 01 (one) coat with approved brand & shade Distemper Paint (Asian / Dulux / Salimar / Berger) on old / new surface including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	25,000		
49	Painting Distemper 02 (two) coats				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing & Painting 02 (two) coats with approved brand & shade Distemper Paint (Asian / Dulux / Salimar / Berger) on old / new surface including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	40,000		
50	Painting Distemper 02 (two) coats over a coat of primer				
	Providing & Painting 02 (two) coats with approved brand & shade Distemper Paint (Asian / Dulux / Salimar / Berger) on old / new surface over a coat of primer including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,000		
51	Painting Plastic emulsion paint 01 coat				
	Providing & Painting 01 (one) coat with approved brand & shade Plastic Emulsion Paint (Asian / Dulux / Salimar / Berger) on old / new surface including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T & P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	200		
52	Painting Plastic emulsion paint 02 coats				
	Providing & Painting 02 (two) coat with approved brand & shade Plastic Emulsion Paint (Asian / Dulux / Salimar / Berger) on old / new surface including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,500		
53	Painting Plastic emulsion paint 02 coats over a coat of primer				
	Providing & Painting 02 (two) coat with approved brand & shade Plastic Emulsion Paint (Asian / Dulux / Salimar / Berger) over a coat of acrylic primer on old / new surface including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	500		
54	Acrylic Wall Putty (water based)				
	Providing & applying acrylic wall putty (water based) to get a smooth surface with approved brand & shade wall putty (JK White/ Birla) on old / new surface including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,200		
55	Painting Synthetic enamel paint 01 coat				
	Providing & Painting 01 (one) coat with approved brand & shade Synthetic enamel Paint (Asian / Dulux / Salimar / Berger) on old wooden/ masonry/ steel surface including thorough cleaning, rubbing out loose scales etc and preparation of the surface area of application, including all cost, conveyance, T & P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	5,000		
56	Painting Synthetic enamel paint 02 coats				
	Providing & Painting 02 (two) coat with approved brand & shade Synthetic enamel Paint (Asian / Dulux / Salimar / Berger) on new/old wooden/masonry/ steel surface including thorough cleaning, rubbing out loose scales etc and preparation of the surface area of application, including all cost, conveyance, T & P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	8,000		

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
57	Painting Synthetic enamel paint 02 coats over a coat of primer				
	Providing & Painting 02 (two) coat with approved brand & shade Synthetic enamel Paint (Asian / Dulux / Salimar / Berger) on old / new wooden or steel surface over a coat of wood primer including thorough cleaning, rubbing out loose scales etc and preparation of the surface area of application, including all cost, conveyance, T & P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	500		
I	Wood Work				
58	Supplying and Fixing Sal wood choughath for door / window				
	Supplying, making and fixing in position Dressed seasoned sal wood work for choughaths of doors, windows, ventilators AC frames etc including all cost of materials & labours, conveyance, royalties, T&P, Scaffoldings, sundries etc complete in all respect as per the direction of the Engineer in charge.	Cum	1		
59	Supplying and Fixing 32mm Piasal or local teak wood panelled shutter				
	Supplying, making and fixing in position Dressed seasoned Piasal or local teak wood work for 32mm thick panelled door/ window shutters including all cost of materials & labours, conveyance, royalties, T&P, Scaffoldings, sundries etc complete in all respect as per the direction of the Engineer in charge.	Sqm	50		
60	Supplying and Fixing 32mm thick single leaf commercial flush door				
	Supplying, fitting and fixing in position Factory made 32mm thick single leaf termite proof commercial flush door conforming to IS:2202 (part 01/1991) of approved brand (Aeon/ Green/ Century) with select seasoned timber and block board core framed with seasoned hard wood battens and bonded at high pressure with phenol form including all cost of materials & labours, conveyance, royalties, T&P, Scaffoldings, sundries etc complete in all respect as per the direction of the Engineer in charge.	Sqm	50		
61	Supplying and fixing 25mm. thick PVC door frame and shutter				
	Supplying, fitting & fixing in position 25mm thick PVC Door of Sintex Make or any equivalent approved make with frame of 40mm x 48mm and all fittings and fixtures such as aluminium handles, hinge, aldrop, tower bolt with screws, nails etc, putty and plaster work after removing the old existing choughaths and shutter and stacking the same for reuse and making good to all damages in wall and floor including all cost of materials & labours, conveyance, royalties, T&P, Scaffoldings, sundries etc complete in all respect as per the direction of the Engineer in charge.	Sqm	20		
62	Making and Fixing of Door / Window choughaths with salvaged wood				
	Making and fixing of door/window Choughaths with salvaged old woods and fittings from old shutters including supplying and fixing necessary screws, nails etc, including all cost & labours, conveyance, royalties, T&P, Scaffoldings, sundries etc complete in all respect as per the direction of the Engineer in charge.	Cum	1		
63	Making and fixing of Door / Window shutters with Salvaged wood				
	Making and Fixing of door/window shutters with salvaged old woods and fittings from old shutters including supplying and fixing necessary screws, nails etc, including all cost & labours, conveyance, royalties, taxes, T&P, Scaffoldings, sundries etc complete in all respect as per the direction of the Engineer in charge.	Sqm	100		
64	Easing of Door / Window				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Easying door/window frame, shutter and fittings after minor modifications / repairing on its position to make it easy closing and opening including supplying and fixing necessary screws, nails etc, including all cost & labours, conveyance, royalties, T&P, Scaffoldings, sundries etc complete in all respect as per the direction of the Engineer in charge.	No	1,500		
65	Supplying and Fixing 12mm thick commercial ply				
	Supplying, fitting and fixing in position 12mm thick termite proof commercial ply of approved make (Aeon / Green / Century) including all cost of all materials & labours, conveyance, T&P etc complete in all respect as per the direction of Engineer-in-charge.	Sqm	50		
66	Supplying and Fixing 19mm thick commercial ply				
	Supplying, fitting and fixing in position 19mm thick termite proof commercial ply of approved make (Aeon / Green / Century) including all cost of all materials & labours, conveyance, T&P etc complete in all respect as per the direction of Engineer-in-charge.	Sqm	20		
67	Aluminium fittings for doors / windows - Aldrop/ sliding bolt 250mm x16mm				
	Supplying and fixing approved brand heavy duty anodised aluminium door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Aldrop/ sliding bolt 250mm x16mm	No	50		
68	Aluminium fittings for doors / windows - Tower bolt 200mm x10mm				
	Supplying and fixing approved brand heavy duty anodised aluminium door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Tower bolt 200mm x10mm	No	20		
69	Aluminium fittings for doors / windows - Tower bolt 150mm x10mm				
	Supplying and fixing approved brand heavy duty anodised aluminium door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Tower bolt 150mm x10mm	No	30		
70	Aluminium fittings for doors / windows - Bow handle 100mm				
	Supplying and fixing approved brand heavy duty anodised aluminium door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Bow Handle 100mm	No	30		
71	CP iron (MS) fittings for doors / windows - Aldrop/ sliding bolt 250mm x16mm				
	Supplying and fixing approved brand Heavy duty Chromium Plated Iron (CP) door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Aldrop/ sliding bolt 250mm x16mm	No	50		
72	CP iron (MS) fittings for doors / windows - Tower bolt 200mm x10mm				
	Supplying and fixing approved brand Heavy duty Chromium Plated Iron (CP) door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Tower bolt 200mm x10mm	No	100		

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
73	CP iron (MS) fittings for doors / windows - Tower bolt 150mm x10mm				
	Supplying and fixing approved brand Heavy duty Chromium Plated Iron (CP) door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Tower bolt 150mm x10mm	No	300		
74	CP iron (MS) fittings for doors / windows - Bow handle 100mm				
	Supplying and fixing approved brand Heavy duty Chromium Plated Iron (CP) door/ window fittings including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Bow handle 100mm	No	300		
75	Oxidised iron butt hinges for doors / windows - Hinges 125mm				
	Supplying and fixing approved brand heavy duty Oxidised Iron Butt Hinges to door/ window including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Hinges 125mm	No	30		
76	Oxidised iron butt hinges for doors / windows - Hinges 100mm				
	Supplying and fixing approved brand heavy duty Oxidised Iron Butt Hinges to door/ window including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Hinges 100mm	No	300		
77	Oxidised iron butt hinges for doors / windows - Hinges 75mm				
	Supplying and fixing approved brand heavy duty Oxidised Iron Butt Hinges to door/ window including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Hinges 75mm	No	500		
78	Oxidised iron butt hinges for doors / windows - Hinges 50mm				
	Supplying and fixing approved brand heavy duty Oxidised Iron Butt Hinges to door/ window including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - Hinges 50mm	No	20		
79	Door Stopper - medium duty				
	Supplying and fixing approved brand medium duty aluminium / wrought iron door stopper to doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	40		
80	PVC wall buffer upto 75mm				
	Supplying and fixing approved brand PVC Wall buffer upto 75mm depth to doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	10		
81	Auto Hinges for Wardrobe doors				
	Supplying and fixing of approved brand Auto Hinges for Wardrobe, Cabinet or Cup board doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	60		
82	Lock for Wardrobe / Wall Almirah doors (Heavy Duty)				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Supplying and fixing of approved brand Heavy Duty Locks for Wardrobe, Cabinet or Cup board doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	20		
83	Bow Handle for Wardrobe / Wall Almirah doors (Decorative), size - 100 mm				
	Supplying and fixing of approved brand Decorative Bow Handle of size 100mm for Wardrobe, Cabinet or Cup board doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	20		
84	UPVC Sliding Door Roller				
	Supplying and fixing of approved brand Heavy Duty (100kg Capacity) UPVC Sliding Door roller including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	20		
85	UPVC Sliding Door Handle				
	Supplying and fixing of approved brand Heavy Duty UPVC Sliding Door Handle including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	10		
86	UPVC Sliding Window side lock set				
	Supplying and fixing of approved brand Heavy Duty UPVC Sliding Window side lock set including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	10		
87	Hydraulic Door closer				
	Supplying and fixing approved brand (Godrej / Hyper/ equivalent make) heavy duty hydraulic door closure to doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	10		
88	Mortice Lock 6 lever				
	Supplying and fixing approved brand (Godrej / Link/ equivalent make) heavy duty Mortice Lock (6- lever) to doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	10		
89	Hydraulic floor springs for aluminium Glass doors				
	Supplying and fixing approved brand (Godrej / equivalent make) heavy duty hydraulic floor spring to aluminium Glass doors including all cost of materials, stainless steel screws, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	8		
J	Glass Work				
90	4mm Pin pointed / ribbed glass panes				
	Supplying, cutting to size and fixing 4mm thick pin pointed / ribbed / frosted glass panes in the windows and ventilators with glass putty, nails, screw etc after removing damaged glass panes if required including all cost of materials, conveyance, labour charges, T&P, scaffoldings, sundries etc. complete in all respect as per direction of Engineer in Charge	Sqm	10		
91	4mm thick plain glass panes				
	Supplying, cutting to size and fixing 4mm thick plain cleared glass panes in the windows and ventilators with glass putty, nails, screw etc after removing damaged glass panes if required including all cost of materials, conveyance, labour charges, T&P, scaffoldings, sundries etc. complete in all respect as per direction of Engineer in Charge	Sqm	10		

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
92	5mm thick Heat Reflecting Glass				
	Supplying, cutting to size and fixing 5mm thick plain / coloured heat reflecting glass panes (Saint Gobain or equivalent) in UPVC / Aluminium doors, windows and ventilators with all required consumables for fixing the new glass pane, nails, screw etc after removing damaged glass panes if required including all cost of materials, conveyance, labour charges, T&P, scaffoldings, sundries etc. complete in all respect as per direction of Engineer in Charge	Sqm	20		
K	Dismantling/ Removing/ Cleaning Work				
93	Removing Cement Plaster				
	Removing old cement plaster of all thickness from walls including racking out joints at all levels and elevations and removing the debris within 50mtr lead including conveyance, labour charges, T&P, scaffoldings, sundries etc. complete in all respect as per direction of Engineer in Charge	Sqm	5,000		
94	Dismantling Brick / Stone masonry of Cement Mortar				
	Dismantling of Brick or stone masonry at all levels and elevations, stacking the useful materials for re-use and disposing the debris within 50 mtr lead including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	250		
95	Dismantling Flooring				
	Dismantling of all type of flooring (AS/ Tile/ marble/ granite) at all levels and elevations, stacking the useful material for re-use and disposing the debris upto a lead of 50mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	2,000		
96	Dismantling Plain Cement Concrete				
	Dismantling of Plain Cement Concrete work at all levels and elevations, stacking the useful materials for re-use and disposing the debris upto a lead of 50mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	25		
97	Dismantling Reinforced Cement Concrete				
	Dismantling of Reinforced Cement Concrete work (RCC work) at all levels and elevations manually or mechanically as suitable, stacking the use ful materials for re-use and disposing the debris upto a lead of 50 mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	10		
98	Dismantling AC/ GCI Sheeting				
	Dismantling / removing of all type of AC / GCI Sheeting work at all levels and elevations manually or mechanically as suitable using cutting gas if required and stacking the steel materials properly upto a lead of 50 mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	500		
99	Dismantling door / windows/ ventilators				
	Dismantling / removing of all type of doors/ windows/ ventilators etc at all levels and elevations manually or mechanically as suitable using cutting gas if required and stacking the steel and wooden materials properly upto a lead of 50mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	500		
100	Removing Old Tarfelt from Roof Slab				
	Removing Old Tarfelt from roof slab, cleaning the surface, lowering and removing the debris within 50mtr lead including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	2,000		
101	Man power for Dismantling of PH and Sanitary Items				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing required Man power for Dismantling / Removing of all type of white vetrious water closets (IWC/ EWC), urinals with all fittings, GI and PVC Pipe Lines etc at all levels and elevations and disposing the debris upto a lead of 50 mtrs including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	No	25		
L	Miscellaneous Work				
102	Supplying and Fixing of Aluminium Sliding Door/window.				
	Supply, fitting, fixing up doors/ window (sliding type) made up of Aluminium section 151-154, 151-155, 151-153 and 151-167 as shutter frame with 5mm thick black glass as panel fitted with rubber bending incuding locking arrangement & fittings including cost of all materials, labour, T&P etc complete as per the direction of engineer in charge.	Sqm	15		
103	Wet Mix Macadam (WMM)				
	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed materialby tipper to site, laying in uniform layers with pavers in sub-base/ base course on well prepared surface and comacting with vibratory roller to achive the desired density as per clause 406 of MORTH specification for road and bridge work (4th Revision) including cost of all materials, Royalties of all materials, labour, T&P etc complete as per the direction of engineer in charge.	Cum	20		
104	Supplying & Spreading HG stone metals 40mm size				
	Supplying and spreading Hard granite stone metals of 40 mm size including cost of all materilas, labour, conveyance, royalty, etc complete as per direction of Engineer-in-Charge	Cum	20		
105	Engagement of High Skilled Manpower				
	Engagement of High skilled man power (Carpenter 1st class / Mason 1st class / Fitter 1st Class/ Welder 1st Class etc.) for miscellaneous work including cost of labour, conveyance, T&P etc. complete as per direction of Engineer-in-charge.	No	20		
106	Engagement of Skilled Manpower				
	Engagement of skilled man power (Carpenter / Plumber / Mason / fitter / welder/ painter etc) for miscellaneous work including cost of labour, conveyance, T&P etc. complete as per direction of Engineer-in-charge.	No	60		
107	Engagement of Semi-Skilled Manpower				
	Engagement of semi-skilled man power (Semi skilled helper) for miscellaneous work including cost of labour, conveyance, T&P etc. complete as per direction of Engineer-in-charge.	No	100		
108	Engagement of Un-skilled Manpower				
	Engagement of Un-skilled man power (Unskilled labour) for miscellaneous work including cost of labour, conveyance, T&P etc. complete as per direction of Engineer-in-charge.	No	200		
109	Providing Steel Scaffolding				
	Providing, mobilising and erecting Steel Scaffolding as per OPGC safety standard with all safety measures, platforms, toe guards, ladders etc for specialised high rise work upto 15 meters height including dismantling, removing and demobilising the scaffolding materials from site after the completion of work, complete in all respect including all cost, conveyance, labour charges etc complete as per the direction of Engineer in charge.	Sqm	1,800		
110	Providing False ceiling				

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	Providing, fitting and fixing of false ceiling with aluminium anodised T-section no 3215 with 2'-0" centre to centre, L-section no-1705 upto 15 micron on 4 walls to be fixed by means of steel screw and PVC plug and the aluminium grid 2'x2' suspended from ceiling etc complete with required quantity of gypboard / perforated asbestos ceiling boards of approved make at all levels and elevations including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In-Charge	Sqm	20		
111	Wall writing / painting				
	Writing on sign boards / walls etc of all letter & size with synthetic enamel paint base and lettering at all levels and elevations including all cost of materials, conveyance, scaffolding, T & P , sundries etc. complete as per direction of Engineering-in-charge.	Sqm	20		
112	Radium stikering/ writing				
	Writing on sign boards / walls etc of all letter & size with Radium stikering and writing with base and lettering at all levels and elevations including all cost of materials, conveyance, taxes, scaffolding, T & P , sundries etc. complete as per direction of Engineering-in-charge.	Sqm	10		
113	AC / Exhaust fan hole Opening				
	Making of window AC opening and Exhaust fan hole opening of all sizes on existing brick masonry wall at all levels and elevations including dismantling of brick work, fixing and grouting of frame of AC & Exhaust fan, making good to all damages, disposal of debris up to lead of 50 mtrs, plastering, distemper matching the wall colour & painting the frame with enamel paint two coats with approved paint including all cost of materials, conveyance, scaffolding, T & P , sundries etc. complete as per direction of Engineering-in-charge.	No	25		
114	Providing APP Membrane 3mm thick				
	Providing and laying 3mm thick APP membrane (Atactic Ploy Propylene modified bitumen based water proofing membrane with non woven polyester felt reinforcement with natural mineral slate finish) on the roof surface over a coat of bitumen primer for bitumen membrane of same manufacturer @ 0.40 Ltr/ Sqm after cleaning the surface thoroughly from all loose and friable products, cement laitance, oil and grease by using butane torch and sealing all joints etc complete including cost of all labour, materials, transportation, sundries and T&P etc complete in all respect as per the direction of the Engineer-In-Charge. (APP Membrane : SikaBit T 130 MG or equivalent)	Sqm	4,000		
M	Sanitary Work				
115	Supplying and Fixing 160mm dia PVC SWR pipe (type-A) Regular				
	Supplying & fixing PVC SWR pipe (type-A), working Pressure 4kg/cm2, Regular quality of approved make (Finolex/Supreme/ equivalent) with all fittings, clamps, plain bends, door bends, Tee, sockets etc including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - 160mm dia PVC SWR pipe (type-A) Regular, working pressure 4kg/cm2, with fittings	Rmt	20		
116	Supplying and Fixing 110mm dia PVC SWR pipe (type-A) Regular				
	Supplying & fixing PVC SWR pipe (type-A), working Pressure 4kg/cm2, Regular quality of approved make (Finolex/Supreme/ equivalent) with all fittings, clamps, plain bends, door bends, Tee, sockets etc including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - 110mm dia PVC SWR pipe (type-A) Regular, working pressure 4kg/cm2, with fittings	Rmt	500		

BOQ & PRICE BID FORMAT					
AMC for Civil Maintenance Jobs in ITPS Colony for 02 Years					
SI	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
117	Supplying and Fixing 75mm dia PVC SWR pipe (type-A) Regular				
	Supplying & fixing PVC SWR pipe (type-A), working Pressure 4kg/cm ² , Regular quality of approved make (Finolex/Supreme/ equivalent) with all fittings, clamps, plain bends, door bends, Tee, sockets etc including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - 75mm dia PVC SWR pipe (type-A) Regular, working pressure 4kg/cm ² , with fittings	Rmt	150		
118	Supplying & fixing PVC P or S trap (Heavy Duty)100mm dia for Water Closet				
	Supplying & fixing PVC P or S trap (heavy Duty) of 100mm dia for water closet with all fittings of approved make (Finolex/ Supreme/ equivalent), jointing the pan with cement mortar 1:1, inclding all cost of materials, Royalties, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	25		
119	Supplying & fixing PVC floor trap 100mm dia (Heavy duty) for bath room and Kitchen				
	Supplying & fixing PVC Floor trap (heavy duty), P or S of 100mm dia with all fittings of approved make (Finolex/ Supreme/equivalent) for bath room and kitchen, jointing the trap with cement mortar 1:1, including all cost of materials, conveyance, royalties, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	25		
120	Supplying & fixing IWC 580mm long				
	Supplying & fixing White vetreous Sanitary Fittings Indian water closet pan (IWC) of approved make (Peryware/ Hindware/ equivalent), duly embedded in cement concrete 1;4:8 using hard granite crusher broken chips 40mm size, including all cost of materials, conveyance, royalties labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - 580mm long	No	20		
121	Supplying & fixing IWC 500mm long				
	Supplying & fixing White vetreous Sanitary Fittings Indian water closet pan (IWC) of approved make (Peryware/ Hindware/ equivalent), duly embedded in cement concrete 1;4:8 using hard granite crusher broken chips 40mm size, including all cost of materials, conveyance, royalties, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge - 500mm long	No	20		
122	Manpower for Joint repairing with applying white cement				
	Providing required Manpower/ plumber for Joint repairing of Floor or pan traps by removing and cleaning the old joint materials, properly applying white cement to the leakage joints including all cost of materials, conveyance, labour charges, T & P, Scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	No	30		
TOTAL VALUE IN INR (EXCLUDING GST)					
GST shall be extra at actuals					