

## **BOQ & PRICE BID FORMAT**

**Name of the work :-"Construction of path way inside PTP area ,OPGC-II ".**

<b>Sl.No.</b>	<b>Item description</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate</b>	<b>Amount (Rs)</b>
1	Fine dressing of earth work in ordinary or hard soil in road formation according to the direction of the EIC including cutting or filling earth upto 0.15m depth of surface including all cost of labour,T&P, etc. complete as per direction of Engineer-in-charge.	Sqm	180000		
2	Earth work in ordinary soil within 50m.initial lead and 1.5m.initial lift including rough dressing and breaking clods to maximum 5 to 7 cm. and laying in layers not exceeding 0.3m.in depth and as per direction of Engineer-in-charge.	Cum	840		
3	Back filling in foundation with excavated materials in layers including watering & ramming with rammers including all cost of labour,T&P, taxes etc. complete as per direction of Engineer-in-charge.	Cum	280		
4	Supplying and Filling of sand in foundation and plinth, watering and ramming including all cost, conveyance, T& P, taxes & duties of all materials and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	12.25		
5	25mm.thick A.S. flooring in c.c.(1;2;4) using 12-20mm size hard granite chips including watering,curing, cost, conveyance, royalties, taxes of all materials and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	2940		
6	Providing and laying of ash bricks 25cm x 12cm x 8cm size) with 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. including all cost of labour,T&P, etc. complete as per direction of Engineer-in-charge.	Sqm	2940		
<b>TOTAL VALUE IN INR (EXCLUDING GST)</b>					
<b>GST SHALL BE EXTRA AT ACTUALS</b>					