

<b>BOQ &amp; Price Bid Format</b>					
<b>Development of Rajib Gandhi Ground at ITPS Colony</b>					
<b>SI No</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Unit Rate (Rs.)</b>	<b>Amount (Rs.)</b>
<b>1</b>	<b>Earth excavation, transportation, filling, levelling &amp; compaction by mechanical means</b>				
	Excavation of any approved type of soil in approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within initial lead of 1 KM on properly prepared and scientifically approved surface including spreading and levelling the earth in 225mm layers, watering earth work upto OMC condition and compaction by sheepfoot rollers and dozer in layers not exceeding 225mm to 95% dry density including hire and running charges of all the machineries, construction, maintenance, watering and lighting of haul road and borrow area etc. complete as per direction of Engineer-in-charge. (measurement of the fill to be taken on the finished compacted section under OMC condition).	Cum	7,650		
<b>2</b>	<b>Engagement of Semi-Skilled Manpower</b>				
	Engagement of semi-skilled man power ( Semi skilled helper ) for miscellaneous work including cost of labour, conveyance, T&P etc. complete as per direction of Engineer-in-charge.	Man days	30		
<b>3</b>	<b>Engagement of Un-skilled Manpower</b>				
	Engagement of Un-skilled man power (Unskilled labour) for miscellaneous work including cost of labour, conveyance, T&P etc. complete as per direction of Engineer-in-charge.	Man days	90		
<b>TOTAL VALUE IN INR (EXCLUDING GST)</b>					
GST shall be extra at actuals					