

Sheeting of Track Hopper OPGC-I					
Bill of Quantities					
SI No	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
<b>1</b>	<b>Dismantling AC/ GCI Sheeting</b>				
	Dismantling / removing of all type of AC / GCI Sheeting work at all levels and elevations manually or mechanically as suitable using cutting gas if required and stacking the steel materials properly upto a lead of 50 mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	7,300		
<b>2</b>	<b>Supplying &amp; Fixing Colour Coated Sheet 0.53mm (TATA Bluescope)</b>				
	Supply and fixing of colour coated trapezoidal sheets of TATA Bluescope Steel make (Lysaght Trimdek 1072 profile 0.53 mm TPT, 0.45mm BTM, AZ150 G550 Colour bond) including cost of 55x8mm self driven screws as required for fixing the sheets complete including conveyance, lead and lift at site & labour charge required for the work all complete as per the direction of the Engineer-In-Charge.	Sqm	7,300		
<b>3</b>	<b>Supplying &amp; Fixing Colour Coated Ridge 610mm grith (TATA Bluescope)</b>				
	Supply and fixing of colour coated trapezoidal Ridge of 610mm grith of TATA Bluescope Steel make (to match Lysaght Trimdek 1072 profile, 0.53 mm TPT, 0.45mm BTM, AZ150 G550 Colour bond) including cost of 55x8mm self driven screws as required for fixing the Ridge complete including conveyance, lead and lift at site & labour charge required for the work all complete as per the direction of the Engineer-In-Charge.	Rmt	570		
<b>4</b>	<b>Earth excavation/ levelling &amp; dressing etc by JCB</b>				
	Earth excavation/ levelling & dressing etc by using JCB in mechanized manner including all costs, conveyance, fuels, mobilisation & demobilisation at site, T&P & labour charges etc, complete in all respect as per the direction of Engineer-in-charge as and when required.	Hour	20		
<b>5</b>	<b>PCC ( 1:3:6 ) 25 to 40mm graded HG chips</b>				
	Cement Concrete (1:3:6) by using 25 to 40mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T&P, royalties of all materials, scaffolding & labour charges etc. complete as per direction of Engg.-in-Charge.	Cum	27		
<b>6</b>	<b>Transportation of debris</b>				
	Transportation of debris / surplus spoil away from work site upto a lead of 5 kilometres by tractor including all cost, conveyance, fuels, loading & unloading, labour charges etc complete as per the direction of Engg.-in-charge.	Cum	300		
	<b>Total</b>				
<b>(GST Extra as applicable indicated in your Price Bid )</b>					