

AWRS Inside Plant Boundary Pipe Line Civil Work BOQ

NAME OF WORK:-

ITEM NO	ITEM DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
1	Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge	cum	4,169.88		
2	Filling in foundation and plinth with excavated materials including watering and ramming as directed by the Engineer-in-charge	cum	3,956.32		
3	Plain Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications. PCC Grade M15	cum	49.58		
4	Cement concrete M25 grade with crushed granite coarse aggregate of size 20mm and down graded mixed in batching and mixing plant including cost of all materials, machineries and labour.	cum	205.49		
5	Providing supplying , lifting , shifting , cutting, bending , fabricating , fitting of reinforcement HYSD bar (Fe500)	MT	20.55		
6	Conveyance of precast sleeper (including loading & unloading) to placement spot and aligning & fixing complete in all respect.	Nos	162.00		
7	Supply, Fabrication, Shifting, Lifting & Erection of Structural steel	MT	9.26		
	Total Gross Amount				

Amount In Words:-

Note :- THE ABOVE RATES ARE EXCLUDING GST.