

ANNEXURE-II**Name Of Work:- SUPPLY OF MATERIALS FOR ROAD WORK FOR BTG INSIDE AND PERIPHERIAL ROAD AREA
UNIT #3&4.**

SL NO	ITEM DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
1	Providing/ Supplying granite broken stone of size not less than 0.0025cum. stacked including Transporting, loading & un-loading ,royalty, taxes of all materials, Tool & Plant machinery & etc. complete as per direction of Engineer - in - charge. (NOTE :- Measurement will be taken as truck volume and 15% void will be deduct from total supplied quantity at time of payment).	cum	4646.00		
2	Providing/ Supplying Crusner broken Granite stone metal 40 to 90mm including Transporting, loading & un-loading ,royalty, taxes of all materials, Tool & Plant machinery & etc. complete as per direction of Engineer - in - charge. (NOTE :- Measurement will be taken as truck volume and 7.5% void will be deduct from total supplied quantity at time of payment).	cum	1374.00		
3	Providing /Supplying stone screened dust passing through 2.36mm sieve and retained on 0.075mm sieve. including Transporting , loading , unloading,royalty , taxes of all materials, Tool & Plant machinery and labour charges etc. complete as per direction of Engineer-in-charge.	cum	787.00		
GST for supply to be extra at actuals		TOTAL AMOUNT			
Amount In Words:-					