

PRICE BID FORMAT

External Repairing & Painting of D-type Block (Phase-III)

Bill of Quantities

SI No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
1	Ash brick masonry (1:6) in Superstructure				
	Ash brick masonry in cement mortar(1:6) in Superstructure for all type of works of all thickness including all cost, splays cutting, watering, curing, conveyance, T & P, Scaffoldings, royalties of all materials and labour charges etc. complete as per direction of Engg.-in-charge. (Ash brick will be supplied from Ash Brick Plant of OPGC free of cost. Contractor has to arrange his own conveyance for transportation to Site)	Cum	1		
2	12mm cement plaster (1:6)				
	Providing 12mm. thick cement plaster in cement mortar (1:6) over masonry / CC work, finished smooth after racking out joints including all cost, watering, curing, conveyance, T& P, royalties of all materials, scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	1,250		
3	PCC (1:2:4) 12 to 20mm graded HG chips				
	Cement Concrete (1:2:4) using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials required for the work, Scaffolding & labour charges etc complete as per direction of Engineer-in-charge	Cum	1.5		
4	25mm Grading Concrete (1:2:2) on roof slab				
	Providing and laying 25mm thick grading concrete (1:2:2) on roof slab using 6mm and down graded size hard granite chips for old work including all cost, conveyance, royalties and labour charges etc complete as per the direction of the Engineer-In-Charge.	Sqm	200		
5	RCC (1:1.5:3) 12 to 20mm graded HG Chips				
	Reinforced cement concrete(1:1.5:3) for all type of work using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials required for the work, Scaffolding & labour charges etc complete as per the direction of Engineer-in-charge. Reinforcement rod and centering and shuttering will be paid separately.	Cum	1		
6	Lift charges for Cement Concrete Work above Ground Floor upto First Floor				
	Extra for Lift charges for all type of cement concrete work above ground floor upto First Floor or a part there of.	Cum	2.5		
7	Centering and shuttering work (Form work) - Roof Slab				
	Providing and fixing strong, rigid, smooth, levelled, and plumbed CENTERING AND SHUTTERING (Form work) including dismantling the same after the required intervals from the date of casting including cost of all materials, labour, conveyance, loading and unloading, royalties, scaffolding, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge - for RCC Floor and roof slabs, landings, balconies, projecting sun shades and chajjas upto 4.3 meter height	Sqm	27		
8	M.S. Reinforcement bar cutting, binding and placing				
	Straightening, cutting, bending, binding, tying and placing of M.S. Reinforcement bars (Plain or Tor) in position including all cost of M.S. Reinforcement bars & binding wire (20 to 22 gauge), conveyance, T & P, Scaffoldings, labour charges etc. complete as per direction of EIC.	Qntl	0.7		
9	Removing Cement Plaster				
	Removing old cement plaster of all thickness from walls including racking out joints at all levels and elevations and removing the debris within 50mtr lead including conveyance, labour charges, T&P, scaffoldings, sundries etc. complete in all respect as per direction of Engineer in Charge	Sqm	1,250		
10	Dismantling Brick / Stone masonry of Cement Mortar				
	Dismantling of Brick or stone masonry at all levels and elevations, stacking the useful materials for re-use and disposing the debris within 50 mtr lead including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	1		
11	Dismantling Reinforced Cement Concrete				
	Dismantling of Reinforced Cement Concrete work (RCC work) at all levels and elevations manually or mechanically as suitable, stacking the use full materials for re-use and disposing the debris upto a lead of 50 mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	1		

PRICE BID FORMAT

External Repairing & Painting of D-type Block (Phase-III)

Bill of Quantities

SI No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
12	Painting weatherproof exterior emulsion paint 02 coats over a coat of primer				
	Providing and painting with weatherproof anti fungal exterior emulsion paint 02 (two) coats over a coat of primer on old / new surface using approved brand and shade weatherproof paint / primer (Asian / Dulux / Shalimar / Berger) including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including, cost, conveyance, T&P, Scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	9,000		
13	Painting Synthetic enamel paint 02 coat				
	Providing & Painting 02 (two) coat with approved brand & shade Synthetic enamel Paint (Asian / Dulux / Salimar / Berger) on new/old wooden/masonry/ steel surface including thorough cleaning, rubbing out loose scales etc and preparation of the surface area of application, including all cost, conveyance, T & P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,050		
14	Wall writing/ painting				
	Writing on sign boards / walls etc of all letter & size with synthetic enamel paint base and lettering at all levels and elevations including all cost of materials, conveyance, scaffolding, T & P , sundries etc. complete as per direction of Engineering-in-charge.	Sqm	12		
15	Providing steel scaffolding.				
	Providing, mobilising and erecting Steel Scaffolding as per OPGC safety standard with all safety measures, platforms, toe guards, ladders etc for specialised high rise work upto 15 meters height including dismantling, removing and demobilising the scaffolding materials from site after the completion of work, complete in all respect including all cost, conveyance, labour charges etc complete as per the direction of Engineer in charge.	Sqm	1,800		
16	Transportation of debris				
	Transportation of debris / surplus spoil away from work site upto a lead of 5 kilometres by tractor including all cost, conveyance, fuels, loading & unloading, labour charges etc complete as per the direction of Engg.-in-charge.	Cum	17		
TOTAL VALUE IN INR (EXCLUDING GST)					
GST extra at actuals, applicable % along with SAC code to be indicated in your offer					