

Interlocking Paver Block Flooring Work at Hospital & Guest House					
BOQ & PRICE BID FORMAT					
SI	Description	Unit	Qty	Rate (Rs.)	Amount (Rs)
1	Earth excavation in gravelly soil				
	Earth work in excavation up to 1.5m depth in gravelly soil including dressing & levelling the bed & depositing the excavated materials within 50m. initial lead & 1.5m. initial lift with all cost, conveyance, tools & plants, labour, complete as per the direction of Engg.-in-charge.	Cum	450		
2	Dismantling Brick / Stone masonry of Cement Mortar				
	Dismantling of Brick or stone masonry at all levels and elevations, stacking the useful materials for re-use and disposing the debris within 50 mtr lead including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	10		
3	Dismantling Plain Cement Concrete				
	Dismantling of Plain Cement Concrete work at all levels and elevations, stacking the useful materials for re-use and disposing the debris upto a lead of 50mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	335		
4	Transportation of debris				
	Transportation of debris / surplus spoil away from work site upto a lead of 5 kilometres by tractor including all cost, conveyance, fuels, loading & unloading, labour charges etc complete as per the direction of Engg.-in-charge.	Cum	800		
5	Supplying & Filling Sand				
	Supplying and Filling of sand in foundation and plinth, watering and ramming including all cost, conveyance, T& P, royalty and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	225		
6	Ash brick masonry (1:6) foundation				
	Ash brick masonry in cement mortar(1:6) in foundation and plinth for all type of works of all thickness including all cost, splays cutting, watering, curing, conveyance, T & P, Scaffoldings, royalty of all materials and labour charges etc. complete as per direction of Engg.-in-charge. (Ash brick will be supplied from Ash Brick Plant of OPGC free of cost. Contractor has to arrange his own conveyance for transportation to Site)	Cum	9		
7	PCC (1:2:4) 12 to 20mm graded HG chips				
	Cement Concrete (1:2:4) using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials required for the work, Scaffolding & labour charges etc complete as per direction of Engineer-in-charge	Cum	2		
8	12mm Cement plaster (1:6)				
	Providing 12mm. thick cement plaster in cement mortar (1:6) over masonry/ CC work, finished smooth after racking out joints including all cost, watering, curing, conveyance, T& P, royalties of all materials, scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	200		
9	Interlocking Paver Block of 60mm thick				
	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. including all cost of labour, material, conveyance, royalties, loading ,unloading, T&P etc. all complete as per the direction of Engineer-in-charge.	Sqm	2300		

Interlocking Paver Block Flooring Work at Hospital & Guest House**BOQ & PRICE BID FORMAT**

SI	Description	Unit	Qty	Rate (Rs.)	Amount (Rs)
10	Painting Weatherproof exterior emulsion paint 02 coats over a coat of Primer				
	Providing and painting with weatherproof anti fungal exterior emulsion paint 02 (two) coats over a coat of primer on old / new surface using approved brand and shade weatherproof paint / primer (Asian / Dulux / Shalimar / Berger) including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including, cost, conveyance, T&P, Scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	500		
11	Supplying and Fixing 110mm dia PVC SWR pipe (type-A) Regular				
	Supplying & fixing PVC SWR pipe (type-A), working Pressure 4kg/cm2, Regular quality of approved make (Finolex/Supreme/ equivalent) with all fittings, clamps, plain bends, door bends, Tee, sockets etc including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In-Charge - 110mm dia PVC SWR pipe (type-A) Regular, working pressure 4kg/cm2, with fittings	Rmt	15		
TOTAL VALUE IN INR (EXCLUDING GST)					
GST extra at actuals, applicable SAC code along with % to be indicated in your price bid					