

Bill of Quantities					
Evacuation of Ash from BTG Area OPGC-II.					
SL. NO.	DESCRIPTION	UOM	QNTY	RATE (Rs)	AMOUNT (Rs)
1	Loading of ash from BTG area by mechanical means loading into and transportation by mechanical means and unloading the ash within initial lead of 2.00 km on properly prepared and scientifically approved surface including spreading and leveling the ash by use of dozers in 22.5 cm layers to make ready for soil capping but excluding in ash mound for all heights including construction, maintenance, and lighting of haul road and borrow area etc. complete as per the direction of Engineer-in-charge	CUM	50,000		
2	Excavation of any approved type of soil in approved borrow area by mechanical means loading into and transportation by mechanical means and unloading the soil within initial lead of 1 km on properly prepared and scientifically approved surface including spreading and levelling the earth in (200mm thick layer with compacted/ 240 mm thick Loose) including construction, maintenance, watering and lighting of haul road and borrow area and finishing it with required slope including all cost of materials, royalty if any etc. complete as per the direction of Engineer-in-charge.	CUM	10,000		
	Total Amount in (Rs.)				
	GST EXTRA AS APPLICABLE INDICATED IN PRICE BID				