

BILL OF QUANTITY					
Deepening of Pond and Construction of 2 Nos of bathing Steps of Kantatikira village under Kumarbandh GP.					
Sl.No.	Description of item.	Qty	Unit	Rate	Amount
1	Fine dressing on earth work.				
	Fine dressing of earth work in ordinary or hard soil in road formation according to the direction including cutting or filling of earth upto 0.15m depth of surface including all cost, conveyance, taxes and labour charges etc complete as per direction of Engineer-in-charge.	4000.00	Sqm		
2	Dewatering of pond with 5 HP diesel engine including all cost, conveyance, taxes and labour charges etc. complete as per direction of Engineer-in-charge.	60.00	Hr		
3	Earth excavation and transportation by Mech. Means.				
	Excavation, loading and carriage by mechanical means of all kinds of soil including Stoney earth, gravel, moori and slushy etc. interspread with boulders up to 1/2 cum size with all lift and delift including trimming of slopes and bed to design section and depositing the excavated materials away from the work site as per specification and as directed by EIC within all lift and initial lead of 2.00KM from the place of excavation including all cost, conveyance, taxes and labour charges etc. complete as per direction of Engineer-in-charge.	10500.00	Cum		
	For Bathing Steps. (2 Nos)				
4	Earth work excavation.				
	Earth work in excavation in foundation in hard soil including dressing & leveling the bed & depositing the excavated materials within 50m. initial lead & 1.5m. initial lift as per the direction of Engg.-in-charge.	78.00	Cum		
5	Sand Filing with Sand				
	Filling foundation and plinth with sand watered and rammed including all cost, conveyance, taxes of all materials and labour charges etc. complete as per direction of Engineer-in-charge.	17.16	Cum		
6	PCC (1:3:6)				
	Plain Cement concrete(1:3:6) by using 25mm. to 40mm size hard granite crusher broken chips including laying of concrete, watering, curing, cost, conveyance, royalties, taxes of all materials, scaffolding & labour charges etc. complete as per direction of Engg.-in-charge.	22.88	Cum		
7	Brick work in C.M.(1:6) in F&P.				
	Ash brick masonry in cement mortar(1:6) in foundation and plinth including splays cutting, watering, curing, cost, conveyance, royalties, taxes of all materials and labour charges etc. complete as per direction of Engg.-in-charge.(Ash brick will be supplied free of cost at ash brick manufacturing plant)	27.30	Cum		

8	PCC (1:2:4)				
	Plain cement concrete(1:2:4)using 12mm. to 20mm size hard granite crusher broken chips including laying of concrete watering, curing, cost, conveyance, royalties, taxes of all materials required for the work , labour charges, centering, shuttering, scaffolding etc. complete as per direction of Engg.-in-charge.	11.70	Cum		
9	Rigid smooth centering and shuttering for Form work.				
	Rigid smooth centering and shuttering for Form work including dismantling the same after the required date of intervals from the date of casting including cost, conveyance, taxes and labour charges etc. complete as per direction of Engineer-in-charge.	39.00	Sqm		
10	12mm thick cement plaster in CM (1:4)				
	12mm thick cement plaster in CM (1:4) over brick work with cement punning including all cost, conveyance, taxes and labour charges etc. complete as per direction of Engineer-in-charge.	124.80	Sqm		
11	Wall painting/ writing				
	Writing on Sign Board/ walls etc of all letter and size with synthetic enamel paint base and lettering at all levels and elevations including all cost, conveyance, taxes and labour charges etc. complete as per direction of Engineer-in-charge.	2.00	Sqm		
TOTAL IN (RS.)					
GST EXTRA AS APPLICABLE INDICATED IN PRICE BID					