

Bill of Quantities					
Floor Tile Work at DAV Public School					
Sl No	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Dismantling Flooring				
	Dismantling of all type of flooring (AS/ Tile/ marble/ granite) at all levels and elevations, stacking the useful material for re-use and disposing the debris upto a lead of 50mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	950		
2	Removing Cement Plaster				
	Removing old cement plaster of all thickness from walls including racking out joints at all levels and elevations and removing the debris within 50mtr lead including conveyance, labour charges, T&P, scaffoldings, sundries etc. complete in all respect as per direction of Engineer in Charge.	Sqm	100		
3	Supplying & Filling Sand				
	Supplying and Filling of sand in foundation and plinth, watering and ramming including all cost, conveyance, T& P, royalty and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	25		
4	PCC (1:2:4) 12 to 20mm graded HG chips				
	Cement Concrete (1:2:4) using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials required for the work, Scaffolding & labour charges etc complete as per direction of Engineer-in-charge.	Cum	50		
5	Vitrified Floor tiles 600mm size				
	Providing & fixing Vitrified Floor tiles of 600mm x 600mm size of approved make (Somani / Nitco / Kajaria / Johnson / Regency/ equivalent) and approved shade and texture over a bed of average 20mm thick Cement Mortar (1:4) and joints with white cement / tile joint adhesives with required colour pigment including all cost, watering, curing, conveyance, T & P, royalties of all materials, and labour charges etc. complete as per the direction of engineer-in-charge.	Sqm	1050		
6	Transportation of debris				
	Transportation of debris / surplus spoil away from work site upto a lead of 5 kilometres by tractor including all cost, conveyance, fuels, loading & unloading, labour charges etc complete as per the direction of Engg.-in-charge.	Cum	75		
TOTAL AMOUNT IN (RS.)					
GST EXTRA AS APPLICABLE INDICATED IN PRICE BID					