

Development of Concrete Flooring of Yard Conveyor (BCN 26) Walkway at CHP, (OPGC II)					
Bill of Quantities					
Sl No	Description of Items	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Earth work in Excavation				
	Earth work Excavation in hard soil or gravelly soil within 50m initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3 m in depth including cost, conveyance, royalties if any, labour , T&P complete as per direction of Engineer In Charge.	Cum	818		
2	Supplying and Filling of Sand				
	Providing and laying of sand in foundation and plinth with watered and rammed including all cost of labour, T&P, royalties, loading and unloading etc. complete as per direction of Engineer-in-Charge.	Cum	86		
3	PCC (1:4:8) 40mm graded HG metal				
	Cement concrete(1:4:8) by using 40mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties, scaffolding & labour charges etc. complete as per direction of Engineer-in-Charge.	Cum	259		
4	PCC (1:1.5:3) 12 to 20mm graded HG Chips				
	Plain cement concrete(1:1.5:3) for all type of work using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete watering, curing, conveyance, T & P, royalties, Scaffolding & labour charges etc complete as per the direction of Engineer-in-charge.	Cum	345		
5	Centering and shuttering work (Form work)				
	Providing and fixing strong, rigid, smooth, levelled, and plumbed CENTERING AND SHUTTERING (Form work) including dismantling the same after the required intervals from the date of casting including cost of all materials, labour, conveyance, loading and unloading, royalties, scaffolding, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge for RCC Foundation and Footing bases of column, mass concrete, precast slabs etc	Sqm	542		
Total Amount in (Rs.)					
GST EXTRA AS APPLICABLE INDICATED IN PRICE BID					