BID DOCUMENT

Name of the work: "Repairing of D-type Garage and sheeting of security barrack in ITPS Colony."

SAFE & CLEAN POWER IS OUR COMMITMENT

ODISHA POWER GENERATION CORPORATION LIMITED

Ib Thermal Power Station, Banaharpali, Jharsuguda – 768234
(ODISHA)

Email: parthiv.nayak@opgc.co.in
manoj.pradhan@opgc.co.in
pradipta.mohanty@opgc.co.in

ODISHA POWER GENERATION CORPORATION LIMITED
(A Government of Odisha undertaking)
AT-IB THERMAL POWER STATION, PO: BANAHARPALI, DIST: JHARSUGUDA, ODISHA-768234
Phone no: (Land Line No. 06645-289232/221/355/356/245)

NOTICE INVITING TENDER

OPGC invites sealed bids from bona fide and financially sound Registered Agencies /Firms /Companies for execution of the following Works for its Thermal Power Plant at Banharpali.

S/N	Name of the Work	Tender cost(Rs.)	EMD (Rs.)
1	Repairing of D-type Garage and sheeting of security barrack in ITPS Colony	As specified in MSTC	56,000/-

Online EMD Collection:- https://payments.billdesk.com/bdcollect/bd/odishapowergenerationcorporationltd/19850

In addition to the conventional modes of submission, Bank Guarantees in the form of Electronic Bank Guarantee (e-BG) shall be accepted for all purposes including Earnest Money Deposit (EMD)/Bid Security, Performance Security, Defect Liability Security, and Security against Mobilization Advance.

Participation -MSTC

Mandatory Registration: All prospective bidders must register themselves on the MSTC e-Procurement Portal (www.mstcecommerce.com) to participate in the tendering process. Since this tender is hosted and published exclusively on the MSTC platform, bids submitted through any other mode will not be entertained.

Cost of bid document (non-refundable) shall be paid by Demand Draft in favour of OPGC Ltd. drawn on State Bank of India (Code-9510) / Union Bank of India (Code-UBIN0806625) / Central Bank of India (Code-283899) payable at ITPS, Banharpali or ICICI Bank (Code-ICIC0003679) payable at Telenpali. Cost of bid document shall have to be submitted along with the bid and the DD towards the tender cost (separate from EMD) should be prepared on or before the last date of submission/receipt of tender, otherwise the bid shall be liable for rejection. Small scale industries/National Small-Scale Industries Corporation/ MSME firms are exempted from payment of Cost of bid document only if they are entitled for exemption of the offered service. Tenderers seeking exemption shall claim in advance along with the photocopy of Valid Registration Certificates at least two days before the due submission date. However, OPGC reserves the right to accept/ reject the exemption request if the same is found unauthenticated or not relevant to the offered item. In case of any discrepancy found between tender document submitted by the agency and the master copy in our office, the latter should prevail. No claim on this account shall be entertained.

NB: Bidders having the requisite qualifying requirements as specified in the bid document shall only be considered for tender evaluation.

DGM-CONTRACTS

SAFE & CLEAN POWER IS OUR COMMITMENT

OPGC encourages all existing or new vendors/suppliers to register with us as empaneled vendors. Please visit our website www.opgc.co.in for details.

ODISHA POWER GENERATION CORPORATION LIMITED
Ib Thermal Power Station, Banaharpali

Name of the work: "Repairing of D-type Garage and sheeting of security barrack in ITPS Colony"

Bid Document & Instruction to Bidders

Bid Document

The Bid documents consist of the following documents:

1. Copy of NIT
2. Bid document & Instruction to Bidders
3. Qualifying Criteria
4. General Conditions of contract
5. Safety, Health & Environment (SHE) Rules & Regulations for Contractors
6. Scope of Work
7. Special Conditions of Contract
8. Rules and Regulations of the e-Reverse Auction
9. Blank Price bid

Techno-Commercial Bid:

The bidder must Upload the following along with the techno-commercial bid:

1) EMD
2) GST Registration Certificate, Provident Fund Registration Certificate, ESI Registration Certificate and IT PAN.
3) Signed & Stamped Bid Documents (all pages) as a token of acceptance.
4) Filled in and signed formats as specified in Annexure of GCC.
5) Credentials in support of qualifying requirements.
6) Commercial terms and conditions and deviation statement.
7) MSME (Micro/small/medium)/NSIC/SSI status of your firm.
8) Documents and undertakings as per the Qualification criteria requirement.

Instruction to the Bidder:-

1. As the tendering process will be conducted through E-bidding, bidders are required to submit their bids exclusively **via MSTC Portal**. **No hard copy of the bid is required to be submitted by the bidders.**

2. Bidders must not include any price details or price-related information in the techno-commercial bid. Any bidder who includes such information in the techno-commercial bid is liable to be disqualified/rejected.

3. Small scale industries/National Small Scale Industries Corporation/ MSME firms shall be exempted from payment of Earnest Money Deposit/Security Deposit/Tender Fees only if they are entitled for exemption of the offered service. However, OPGC reserves the right to accept/ reject the exemption request if the same is found unauthenticated or not relevant to the offered item.

Qualification criteria

The bidder who wishes to participate in the bidding shall meet the Qualifying Requirements stipulated hereunder:

2.1	**Technical Criteria:**
2.1.1	Bidder must have executed *Similar Work (defined below) in the last seven (07) years in any thermal power plant/other industries of repute as on the date of Techno-Commercial Bid Opening. Credentials for successfully executed similar nature of works must be submitted along with the Bid. Relevant PO copies and Client's completion certificate will be considered as the credential/documentary proof. Similar works shall be considered in either of the following. a) Three completed similar works costing not less than Rs.11.22 Lakh. OR b) Two completed similar works costing not less than Rs.14.03 Lakh. OR c) Single completed similar works costing not less than Rs.22.44 Lakh.
*Similar Work	Similar works means Civil repair works/construction works.
2.2.	**Financial Criteria**
2.2.1	The bidder should be financially sound and shall have average annual financial turnover during last financial year FY-2023-24, FY-2024-25 and FY-2025-26 of minimum Rs.8.5 Lakh. The bidder shall submit audited balance sheet including Profit & Loss statement as documentary evidence in support of the qualifying criteria. For the purpose of calculating financial turnover, revenue from Trading Business and Other Income is not admissible. OR In cases where a bidder is not required to prepare or obtain audited Balance Sheets and Profit & Loss Statements in accordance with the applicable Government Financial Circulars, Acts, Rules, or Regulations, the bidder shall submit certified copies of the relevant financial statements duly certified by a Registered Practicing Chartered Accountant. Notwithstanding anything contained in the above clause, Bidder(s) must not be in loss making financial status and should have a positive net worth during the financial years mentioned above.

2.3	**General Criteria**
2.3.1	Safety requirement-Bidder loss time hours must have been less than 200Hrs in last 3 years. (Contractor's self-certification).
2.3.2	The bidder must have its own Provident Fund Registration certificate, ESI Registration certificate, and Income Tax PAN and GST certificate. Photocopies of these documents must be submitted along with Techno-commercial Bid.
2.3.3	The bidder must submit an undertaking that it is not blacklisted or debarred from participation in tenders during the last 02(Two) years on ground of performance for the similar nature of job. (Contractor's Self Certification) AND Insolvency: Bidder should not be under NCLT, insolvency proceedings, liquidation etc.
Note:	Notwithstanding anything stated above, OPGC reserves the right to assess the capability and capacity of the Bidder to perform the contract should the circumstances warrant such an assessment in the overall interest of OPGC. • For all qualification criteria all supporting documents to be provided. Owner reserves the right to obtain necessary documents and also to assess the qualification of the Bidder, subsequent to submission of bid, as deemed necessary by Owner to establish bidder's qualification. • Sufficient documentary proof in support of the above must be submitted along with the Techno-Commercial Bid. • Tenders submitted without the above techno-commercial requirements shall be liable for rejection. • Any other documents in addition to the above which the applicant wants to submit. • The bidders who are found qualified in the above will be invited for the opening of the price • OPGC reserves the right to do due diligence of the credentials submitted by the bidders.

Scope of Work

Work: Repairing D-type garage and sheeting of security barrack in ITPS Colony

The Contractor shall provide all materials, labour, equipment, tools, supervision, and incidental works required for the repair of garage & sheeting replacement of security barrack as per specifications, and BOQ.

Site Preparation

- Site clearing, setting out, and marking.
- Dismantling of floor, brick wall, concrete, wall as per requirement and disposal of surplus materials.

Civil Works

- Construction of Brick wall, Plastering, and concrete works.
- Formwork, concreting, curing, and roof gridding.

Structural Steel Works

- Supply, fabrication, transportation, and erection of structural steel members as per BOQ.
- Installation of MS Sheet, MS Angles, purlins, bracings, base plates, bolts, and accessories.

Roofing Works

- Installation of roofing sheets with all required fasteners and accessories **(Sheet & MS round pipe will be provided by OPGC & all other materials in agency scope)**.
- Installation of ridge caps, flashings, gutters, and downpipes (if specified).

Protective Coating

- Surface preparation and application of primer, paint, or galvanizing as specified.
- Touch-up painting after erection.

Completion & Handover

- Site cleaning and removal of debris.
- Rectification of defects during the defect liability period

TECHNICAL SPECIFICATION

Name of work: "Repairing D-type garage and sheeting of security barrack in ITPS Colony"

1) The construction materials such as Cement, sand, chips etc. if felt necessary will be subjected to test at the cost and risk of the agency.
2) Any defective material brought to site should be removed by the agency at the instance of department.
3) Agency has to arrange all construction materials such as Cement, Sand, Chips, MS Reinforcement bars, colors, paints, wood, glass, door window fittings, PH materials etc. required for the work as per the item specifications.
4) The quantity mentioned in the schedule of quantities is purely tentative. At any point of time agency may be asked to execute any quantity of work as per the site requirement.
5) All the items mentioned in detail items of the work may be executed at any location and at any height.
6) All the materials are to be approved by concerned Engineer-in-charge before use.
7) All work is to be carried out without causing hindrance to day-to-day activity.
8) Agency has to make his own arrangement of construction water for the works from available points only.
9) Electricity if required by the agency shall be supplied free of cost. Contractor has to make all necessary arrangement for safe supply of electricity but the connection shall be given by department people.
10) Portland Cement of Ultratech, Dalmia, ACC, RAMCO make of PPC 53 grade, confirming to corresponding IS code shall be utilized in the work before the expiry date.
11) MS Reinforcement bars (Tor or Plain) of SAIL / TATA/JINDAL/ Equivalent make of Grade Fe 500 / 550, conforming to IS-1786: 2008 shall be utilized for the work.
12) Paints shall be ASIAN PAINT / BERGER / BIRLA OPUS to be used.
13) Fly Ash Bricks will be supplied free of cost from OPGC Ash Brick Manufacturing Plant. The contractor has to make his own arrangement for transportation of bricks to the construction site. Balance Ash Bricks after completion of work must have to be returned back at the Ash Brick Plant, failing which double the prevailing cost of the fly ash brick will be deducted from the Party's Final Bill.
14) The Contractor has to make his own arrangement for constructing cement and other material go down, workshop, office etc. in the colony premises with due permission from department/ EIC at the allocated space. After expiry of the contract period, the site must have to be cleared and hand over back to EIC prior to final settlement.
15) All the workmen should have gate pass as per OPGC norms.
16) All the vehicles & machineries used for the purpose of the work should have proper documents and driver should have professional license.
17) All materials brought into the site by the contractor are to be recorded at OPGC main gate, the same will be submitted with bill.
18) The raw material brought by the agency should be stacked properly at place shown by department Personal so as not to cause any inconvenience to other people in the area.
19) Use of PPE & Safety rules to be followed as per OPGC norms and regulation without any extra cost.
20) Gate pass will be followed as per OPGC norms and regulations.
21) Security of contractor's equipment, material etc. is of contractor's responsibility.
22) If any damage occurs to work and other structure, then bidder should repair and finish good at his own cost.
23) The bidder shall make all safety precaution for power consuming equipment at its own cost.

24) Skilled work force with experienced supervisor and technical person should be deployed by the bidder with no extra cost to Owner.
25) The bidder shall not claim extra for any wastage, damages of construction material.
26) Bidder shall strictly follow the approved products/brand.
27) Bidder shall keep arrangement for regular housekeeping during and post work, to keep plant / working area clean.
28) The bidder shall arrange dewatering pump, if required with no extra cost to client.
29) All the statutory compliance including ESI to be maintained by the contractor as per OPGC rule.
30) All required PPEs. Like Safety Helmet, Safety Goggles, Hand gloves, Ear plugs, Safety Shoes, Full body harness with double lanyard, dust masks, fall arrestor, etc. are in bidder's scope
31) The contractor is fully responsible for the safety of his workmen and shall provide necessary safety appliances to them and also shall comply with all safety rules and regulations.
32) The contractor has to take special precaution to ensure that the personnel under his control do not carry any combustible materials to work site. Smoking & alcohol is strictly prohibited inside colony premises.
33) The contractor shall ensure that the tools and tackles used for the job are tested and certified by competent person before deployment on job.
34) Any other miscellaneous work not mentioned but required for completion of job is included in the scope of work and contractors will not be paid any extra amount for the same.
35) Roofing Sheets
    Color coated trapezoidal profile sheets.
    Thickness: 0.50 mm minimum.
    Everest/Bhushan or approved equivalent.

SPECIAL CONDITIONS OF CONTRACT

Name of work: "Repairing D-type garage and sheeting of security barrack in ITPS Colony"

1) The period of contract is 04 Months from the date of issue of LOA / Work Order excluding mobilization period of 7 days. The Contractor should mobilize all their resources within the mobilization period to start the work.
2) It is a work contract. The prices quoted by the contractor will remain firm throughout the contract period. Any changes in minimum wages or material rates during the contract period shall be borne by the contractor.
3) The contractor is required to mobilize his men, materials, plant & equipment at his work site within 07 days of intimation to start the work, failing which the Engineer-In-Charge will annul the contract agreement at his discretion. In the event of any such annulment, the owner reserves the right to recover the cost and other financial losses from the contractor in any manner deemed legally correct besides forfeiture of the EMD converted as ISD. The onus of proving that the delay in mobilization was beyond the control lies with the contractor. The Engineer-in-charge after satisfying himself with the reason for the delay if any may allow extension of time to avoid the annulment of the contract.
4) The contractor shall be fully responsible for his workers with regards to terms of employment. OPGC will not be held responsible in any manner whatsoever in respect of worker engaged by the contractor. The contractor should issue Photo ID cards to all his workmen and produce the same as and when required for EIC for verification.
5) 5% of the gross bill amount shall be withheld towards statutory dues, which will be refunded after submission of authenticate document by the contractor.
6) 5% of gross monthly bill will be deducted towards security deposit (SD), which will be released after final bill is settled.
7) Running Bills shall be paid to the contractor after submission of Bill along with prescribed measurement, material statement and statutory documents.
8) The contractor shall disburse the wages to the worker on or before 7th day of completion of the wage period through Bank Payment.
9) The Contractor shall disburse the statutory benefits like bonus, leave encashment etc. of the workers after completion of each year of work.
10) In the event failure of contractor to undertake/attend to any job/ supply of materials specified under the scope within the specified time period, the Engineer-in-charge shall have the right to levy penalty as deemed suitable equal to 10% of the cost for that item of work/ material. Accordingly, the actual billing amount shall stand reduced to the extent of penalty cost imposed /recovered.
11) If any other item which is not mentioned in the bill of quantities, but is required to be executed for maintenance work, the agency will have to execute the same at the schedule of rate of Govt. of Odisha / approved rate of OPGC.
12) The contractor shall abide by the "EHS policy" and General Guidelines for Environmental protection of OPGC.
13) ESI Registration of the Contractor and enrolment of workmen under ESI is Mandatory.
14) The contractor shall abide by the legal provisions with regards to Health, Welfare and Safety of workers engaged by him. He is also responsible for medical care of the person engaged by him.
15) All the staff and workmen as mentioned in the scope of work must undergo safety training.
16) Any defective work noticed within the defect liability period of one year shall be rectified by the contractor immediately on receipt of information with his own cost.
17) Agency has to execute any quantity of work as required however small or large it may be.
18) Agency has to make all arrangements for safe execution of work at any elevation using steel scaffolding positively.
19) Accommodation and conveyance of worker will be in the contractor's scope with no extra cost.
20) Mason, carpenter, welder & gas cutter engaged at site must be skilled and experienced.

Bill of Quantities (BoQ)

Repairing of D-type garage and Sheeting of Security Barrack at ITPS Colony

Sl No	Description	Unit	Estimated Quantity	Unit Rate (In Rs.)	Amount (Rs.)
1	**Ash brick masonry (1:6) in Superstructure**				
	Ash brick masonry in cement mortar(1:6) in Superstructure for all type of works of all thickness including all cost, splays cutting, watering, curing, conveyance, T & P, Scafoldings, royalties of all materials and labour charges etc. complete as per direction of Engg.-in-charge. (Ash brick will be supplied from Ash Brick Plant of OPGC free of cost. Contractor has to arrange his own conveyance for transportation to Site)	Cum	47.840		
2	**PCC (1:3:6) 12 to 20mm graded HG chips**				
	Cement Concrete (1:3:6) by using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T&P, royalties of all materials, scaffolding & labour charges etc. complete as per direction of Engg.-in-Charge.	Cum	38.775		
3	**Supplying & Filling Sand**				
	Supplying and Filling of sand in foundation and plinth, watering and ramming including all cost, conveyance, T& P, royalty and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	25.850		
4	**Fabrication/ erection of iron work**				
	Supplying, Fabrication and erection of all type of Mild steel Iron work (sectional weight upto 19.8 kg/m) for all type of structures, sheds, grills, doors, fencing posts etc with approved quality (SAIL/ Equivalent make) steel structural, angles, channels, plates of all sections at all levels and elevations, painting with 2 (two) coats of high gross enamel paint over a coat of red oxide primer including all cost of materials, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	Kg	455.000		
5	**Supplying & Fixing Colour Coated Trapezoidal sheet**				

	Supply and fixing of colour coated trapezoidal sheets of 0.5mm thick of Everest / Bhusan/ equivalent make including cost of 55x8mm self driven screws as required for fixing the sheets complete including conveyance, lead and lift at site & labour charge required for the work all complete as per the direction of the Engineer-In-Charge.(Sheet will be provided by OPGC)	Sqm	1,177.000		
6	**Repair of M.S doors / grills/ shutters**				
	Labour Charges for Repairing of all type of steel doors, grills, shutters etc on position or at workshop by cutting out the damaged and corroded steel structural, fixing of new steel structural as required by welding (to be paid separately) at all levels and elevations, painting with 2 (two) coats of high gross enamel paint over a coat of red oxide primer including all cost of materials except steel, conveyance, labour charges, T & P, scaffoldings, sundries etc complete in all respect as per direction of Engg- In- Charge	Kg	150.000		
7	**12mm Cement plaster (1:6)**				
	Providing 12mm. thick cement plaster in cement mortar (1:6) over masonry/ CC work, finished smooth after racking out joints including all cost, watering, curing, conveyance, T& P, royalties of all materials, scaffolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	500.000		
8	**25mm Grading Concrete (1:2:2) on roof slab**				
	Providing and laying 25mm thick grading concrete (1:2:2) on roof slab using 6mm and down graded size hard granite chips for old work including all cost, conveyance, royalties and labour charges etc complete as per the direction of the Engineer-In-Charge.	Sqm	385.000		
9	**Removing Cement Plaster**				
	Removing old cement plaster of all thickness from walls including racking out joints at all levels and elevations and removing the debris within 50mtr lead including conveyance, labour charges, T&P, scaffoldings, sundries etc. complete in all respect as per direction of Engineer in Charge	Sqm	115.000		
10	**Dismantling Brick / Stone masonry of Cement Mortar**				
	Dismantling of Brick or stone masonry at all levels and elevations, stacking the useful materials for re-use and disposing the debris within 50 mtr lead including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Cum	47.840		
11	**Dismantling Flooring**				

	Dismantling of all type of flooring (AS/ Tile/ marble/ granite) at all levels and elevations, stacking the useful materal for re-use and disposing the debris upto a lead of 50mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	86.615		
12	**Dismantling AC/ GCI Sheeting**				
	Dismantling / removing of all type of AC / GCI Sheeting work at all levels and elevations manually or mechanically as suitable using cutting gas if required and stacking the steel materials properly upto a lead of 50 mtr including cost, conveyance, T&P, scaffoldings, sundries and labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	132.000		
13	**Painting Weatherproof exterior emulsion paint 02 coats over a coat of Primer**				
	Providing and painting with weatherproof anti fungal exterior emulsion paint 02 (two) coats over a coat of primer on old / new surface using approved brand and shade weatherproof paint / primer (Asian / Dulux / Shalimar / Berger) including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including, cost, conveyance, T&P, Scafolding and labour charges etc complete as per the direction of Engineer-in-Charge.	Sqm	593.25		
14	**Painting Distemper 02 (two) coats over a coat of primer**				
	Providing & Painting 02 (two) coats with approved brand & shade Distemper Paint (Asian / Dulux / Salimar / Berger) on old / new surface over a coat of primer including thorough cleaning, rubbing out moss and loose scales etc and preparation of the surface area of application, including all cost, conveyance, T&P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,609.000		
15	**Painting Synthetic enamel paint 02 coats over a coat of primer**				
	Providing & Painting 02 (two) coat with approved brand & shade Synthetic enamel Paint (Asian / Dulux / Salimar / Berger) on old / new wooden or steel surface over a coat of wood primer including thorough cleaning, rubbing out loose scales etc and preparation of the surface area of application, including all cost, conveyance, T & P, scaffolding & labour charges etc. complete as per direction of Engineer-in-charge.	Sqm	1,188		
16	**Wall writing / painting**				

	Writing on sign boards / walls etc of all letter & size with synthetic enamel paint base and lettering at all levels and elevations including all cost of materials, conveyance, scaffolding, T & P , sundries etc. complete as per direction of Engineering-in-charge.	Sqm	4.050		
17	**Transportation of debris**				
	Transportation of debris / surplus spoil away from work site upto a lead of 5 kilometres by tractor including all cost, conveyance, fuels, loading & unloading, labour charges etc complete as per the direction of Engg.-in-charge.	Cum	139.795		
	Total (In Rs.)				
	GST @18% (In Rs.)				
	Grand Total (In Rs.)				

Rules and Regulations of the e-Reverse Auction

Buyer's Name/Owner	Ib Thermal Power Station (A Unit of Odisha Power Generation Corporation Limited)
Auction To Be Conducted By	MSTC Limited
Name of the work	Repairing of D-type Garage and sheeting of security barrack in ITPS Colony
Date & Time Of Auction	Auction Date: [To be intimated later] Online e-Reverse Auction Time : [To be intimated later] URL: www.mstcecommerce.com/eprochome/opgc
Special Instructions	Bidding in the last minutes and seconds should be avoided in the bidders own interest. Neither the Service Provider nor OPGC will be responsible for any lapses /failure on the part of the vendor, in such cases.
Auto Extension of Closing Time	5 minutes NB: If any bidder quotes 5 minutes before closing time, the closing time will be extended automatically for another 05 minutes and so on till 05 minutes idle time between the bids.
Decremental Value	Minimum decrement will be intimated before E-RA
Start Price	The start bid price as decided by OPGC tender committee shall be displayed at MSTC Limited auction platform during start of the e-RA.

1. The financial bid process will comprise of two rounds. In the first round, the IPO of the techno-commercially qualified bidders will be opened & ranked on the basis of ascending order for determination of qualified bidders. Best five (L-1 to L-5) bidders would be qualified bidders for E-RA and such qualified bidders shall be eligible to participate in the E-RA and submit their FPO with respect to the bid.
2. In case of tie for L5 bid, all the bidders offering L5 will be allowed for e-RA.
3. Bidders must be a registered user to bid for Buyer ("OPGC") in MSTC portal www.mstcecommerce.com/eprochome/opgc. Bidders need to have their Login ID and Password prior to e-Reverse Auction.
4. Bidders have to participate as per the e-Reverse Auction time and date communicated to them & based upon e-Reverse Auction invitation for particular Auction.
5. Quotation once submitted through e-Reverse Auction cannot be withdrawn /deleted. Otherwise, the EMD submitted by the bidder shall stand forfeited.
6. Buyer reserves the right to ban the bidder from participating in e-Reverse Auction without any explanation/reason at any stage of e-Reverse Auction.
7. Buyer reserves the rights to extend / cancel the e-Reverse Auction.
8. E-Reverse Auction shall be conducted in Indian Rupees only.
9. All prices submitted by Bidder in e-Reverse Auction shall be as per Tender's Terms & Conditions.
10. Validity of bids: As mentioned in Tender Document.
11. Written Confirmation shall be taken in advance regarding participation in the e-Reverse Auction to buyer along with the Authorized person name and details.
12. Buyer reserves the right to award the Purchase Order / Service Order as per buyer's discretion irrespective of Live Auction Rank.
13. Buyer reserves the right to repeat the e-Reverse Auction of same package.

14. **After completion of e-Reverse Auction, the lowest evaluated bid of all the bids submitted in manual and e-Reverse Auction process shall be considered for award of the Purchase order / Work order.**
15. The bidders shall quote from their own offices/ place of their choice. Internet connectivity shall have to be ensured by bidders themselves.
16. If the Bidder or any of his representatives are found to be involved in Price manipulation/ cartel formation of any kind, directly or indirectly by communicating with other bidders, OPGC at its own discretion shall debar the bidder from the e-Reverse Auction/Tender and future participation also.
17. OPGC reserves the right to cancel the e-Reverse Auction process/ tender at any time, before ordering, without assigning any reason and may go for manual opening of price bids as per standard practice.

18. OPGC shall not be liable for any interruption or delay in accessing the MSTC portal irrespective of any cause. In such cases, the decision of OPGC shall be binding on the bidders.
19. Other terms and conditions shall be as per NIT, bidder's techno-commercial Bid and other latest correspondences/ final confirmations, (if any) against the NIT.
20. If any item is not quoted by a bidder, the maximum price quoted by the other participated bidders for that item shall be considered for arriving evaluated price of that bidder.
21. The total L1 Price obtained through e-Reverse Auction shall be proportionately distributed among each line item in line with the price quoted and evaluated in the hard copy price bid.
22. The price quoted in e-Reverse Auction is the total price for all the items and quantity as per Price Schedule of NIT irrespective of any omission by the bidder in the hard copy price bid.
23. In case, the L1 Bidder in e-Reverse Auction and manual Tender happens to be the same bidder, then minimum price among both shall be considered as L1. If the bidder disagrees to accept the said condition, then his EMD shall be forfeited. Apart from this the bidder will be debarred from participating in future e-Reverse Auction/Tender of OPGC.
24. Each Bidder shall get the final loading factor (%age of the quoted price) from OPGC before e-Reverse Auction for the deviations, if any, taken by them in the techno-commercial bid.
25. The Price quoted in the e-Reverse Auction shall be inclusive of all applicable taxes, duties and levies, deviations considering the loading factor (got from OPGC/Tender Condition as mentioned in above clause) on his quoted price. However, the GST shall be paid extra as applicable and not included in the loading factor as well as total price.

UNDERTAKING

I hereby undertake that I agree to the **"Rules and Regulations of the e-Reverse Auction"** mentioned herein.

Signature:

Name:

Date:

Company Name: **Seal:**

Signature Not Verified
Digitally signed by MANOJ KUMAR PRADHAN
Date: 2026.11.20 16:26:24 IST
Reason: Secure Document
Location: India